


Search



## ***Model PAF 306-HS, 20" Offset Manhole. MC306 Replacement Pressure Relief Device***

Model 306-HS is a replacement PAF for use on MC306 cargo tanks. This relief vent meets less-than-a-liter surge requirements per §178.345-10(b)(3) and also meets the MC306 set pressure requirements of §180.407(j)(1)(i). A MC306 normal vent is included with assembly. The manhole's overall height is 3.56" from the top surface of the manhole collar.

**Set Pressure:** 3.0 to 4.4 psig  
(20.6 to 30.3 kPa)

**Rated Air Flow:** 294,985 SCFH at 5 psig  
(8,353 SCMh at 34.5 kPa)

**Liquid Flow Capacity:** 1,335 gpm at 5.0 psig  
(5,054 lpm at 34.5 kPa)

**Part Numbers:**

FVAH820BXB – Standard Model (Steel zinc plated cover with nitrile seals)

FVAH863BXB – Self Latch Model (Steel zinc plated cover with nitrile seals)

7556ALBN – Relief Vent Assembly PAF 306-HS

7557BNZC – Relief Vent Assembly PAF 306-HS with strongback.

Alternate seals are available as-well-as a stainless manhole option.

